WF	Indicative location for drinking fountain. Final location to be agreed with engineers.
Item 01	2 shelters - Broxap Blox B cycle shelter with open frontage. Shelter 1 - 12 pupil cycle parking spaces Shelter 2 - 10 staff cycle parking spaces
Item 02	External canopy 5 x 5m square conic by Broxap or similar. Colour Holly Green to canopy and framework
A	Active bay with EV charging
P	Passive bay for future EV charging installation
Item 03	Opportunity for line markings to externals for games and imaginative play. Final design, colour, and games to be agreed with the school during detailed design.
Item 04	Proposed raised timber growing bed
Item 05	Proposed sub-station within secure compound

- Secure line - 2.4m high weldmesh fencing
- 3m high weldmesh sports fence to MUGA
- Internal secure line - 1.8m high weldmesh fencing
- 1.8m high timber closed timberclosed timber fence to bin store
- Existing boundary fenceline retained
- Existing trees retained
  Refer to SRP1055-WWA-XX-XX-T-L-0603 for tree survey and associated AIA
- Proposed tree planting
- Wildflower meadow
- Exisitng vegetation retained
- Amenity grass
- Proposed shrub/ ornamental planting
- Proposed hedge planting
- Proposed rain garden planting with 50mm upstand PCC flat-top edging
- Asphalt surfacing
- Permeable block paving
- Coloured asphalt surfacing to MUGA
- Coloured asphalt surfacing to hard play area
- Access zone to accessible parking bay and no parking area marking
- PCC flag paving, laid staggered pattern
- Blister pavinvg to car park entrance
- Concrete hardstanding to sub-station
- Sheffield cycle hoops
- Benches - final product to be confirmed with the school
- DB — Door Barrier - 1320mm(H) x width varies.
- Bat boxes
  Ecologist to confirm final locations

No.	Date	Appr	Revision Notes
S4C05	09/10/24	LD	Drawing issued for planning.
S4C04	08/01/24	TJ	Layout and key updated
S4C03	12/10/23	TJ	Layout updated. Access path added. Porous asphalt omitted Fence type added. Fence styles amended
S4C02	28/09/23	TJ	Layout updated

Note: All Dimensions must be checked on site and not scaled from this drawing during construction.
All cross references are to the latest revision of the relevant drawing or specification being referenced

© Copyright

wynne-williams associates
landscape architects & arboricultural consultants
2 Threshelfords Business Park, Inworth Road, Feering, Essex CO5 9SE
web: w-wa.co.uk tel: 01376 573050

Scale/North Point: 0 5 10 M

Client: DFE — Department for Education

Main Contractor: Morgan Sindall

Job Title: Burnside PRU

Drawing Title: Site Landscape Plan East

Issue: PLANNING

Scale	Sheet size
1:100 @A1	A1

Drawn	Checked
AM	TJ

Uniclass Code	Date
	20/07/2023

Drg	Status	Rev
SRP1055-WWA-ZZ-ZZ-D-L-0103	S4	C05